BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

NEGOTIATED SCHEDULE - B

Construction of Gym Room above existing Swimming Pool Office Building and other developmental works in Allalasandra Ward No 04 Yelahanka Satellite Town

SNo	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri D K NAGARAJA (D K N AND ASSOCIATES)	
				In figures	In words
1	427.26	Levelling course using Flexible Cementatious Material A concrete mix in the ratio 1:1.5:3 (1 cement : 1.5 quartz powder : 3 graded stone) is laid to make haunch at junction of parapet and roof slab and at damaged portions to drain off water. The factory made dry CEMENTATIOUS silica sand power consisting of dry cement mortar (1 cement : 4 silica sand) shall be mixed with additives like ISOPROOF chemical and acrylic polymer and water to arrive at workable consistency. The same shall be applied over the prepared surface to give even surface and act as base for geotextile fabric.	Sqm	922.00	Rupees Nine Hundred Twenty Two Only
2	0.29	Providing T M T steel reinforcement for R C C work including straightening, cutting, bending, hooking, placing in position lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications TMT Bars Fe 550	MT	82730.00	Rupees Eighty Two Thousand Seven Hundred Thirty Only
3	223.67	Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800 kg/m3 Having aq minimum average compressive strength of 5.00 N /mm2 confirming to IA 2185 (Part q) 2005 and constructed with CM 1:4 as [er IS 2572 2005 including cost of all materials labour charges, scaffolding curing hire charges of machineries etc as per specifications Solid concrete blocks of Size 400x200x200 mm	Sqm	1084.00	Rupees One Thousand Eighty Four Only
4	54.46	Providing and constructing non load bearing wall with solid concrete blocks of size 400x100x200mm having a block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 confirming to IS 2185 (Part 1) 2005 and constructed with CM 1:4 as per IS 2572 2005 including cost of all materials, labour charges, scaffolding, curing, hire charges of machineries etc., complete as per specifications.	Sqm	968.00	Rupees Nine Hundred Sixty Eight Only
5	2.18	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., for all super structure works with all lead and liftetc., complete. (exculsive of cost of steel and fabricationcharges)	Cum	6302.00	Rupees Six Thousand Three Hundred Two Only
6	15.00	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 24kgs. with 12mm and down size graded granite metal coarse aggregates @0.5175cum and fine aggregtes @ 0.345cum, with superplastisizer @0.225lts, machine mixed, well compacted for plain chaja of 7.5 cms. average thickness, upto ground floor level, including cost of all materials, labour,HOM of machinery, finishing, curing, complete as per specifications	Sqm	510.00	Rupees Five Hundred Ten Only

Contractor

Scanned by TapScanner

	Juantity	Item Name	Unit	Negotiated Rates quoted by Sri. D K NAGARAJA (D K N AND ASSOCIATES)	
				In figures	In words
7	32.76	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specificaitons	Sqm	490.00	Rupees Four Hundred Ninety Only
8	15.00	Providing and removing centering, shuttering, strutting, propping etc., for chajas, corbels e tc., including edges including cost of all materials, labour complete as per specificaitons	Sqm	400.00	Rupees Four Hundred Only
9	290.00	Providing and Constructing Standard Rubber Flooring for Indoor Areas using Rubber Memberain of 12mm to 16mm thick, to be layed over Prepared Cement Morter/Concrete surface using CM 1:6 Beneath rubber memvrain including cost of all materials, labour,packing joints and mortar, finishing, curing all lead & lift , transportation and also including all applicable taxes etc., complere as per firection of Engineer in Chrage of Work	Sqm	5132.00	Rupees Five Thousand One Hundred Thirty Two Only
10	540.69	Providing 18mm thick Internal cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering, Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.	Sqm	323.00	Rupees Three Hundred Twenty Three Only
11	179.10	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications and direction of the Engineer in charge.for Outside Plastering	Sqm	312.00	Rupees Three Hundred Twelve Only
12	540.69	Providing applying two coats of wall putty to inside plastered walls and ceiling using white cement putty. Scrapping and levelling the surface using steel blade and preparing the surface even and smooth by using different grade sand papers including cost of all materials cost oif labour and scaffolding etc complete as per the specifications	Sqm	89.00	Rupees Eighty Nine Only
13	540.69	Providing and applying painting in two coats with plastic Emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications and as per the directions of the Engineer in charge. (with Primer)	Sqm	103.00	Rupees One Hundred Three Only
14	179.10	Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to givean even shade after throughly brooming the surface to remove all dirtand loose powdered material, free from mortar drops and other foreign matter cost of materials, labours complete as per specifications.	Sqm	121.00	Rupees One Hundred Twenty One Only

Contractor

Scanned by TapScanner

	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. D K NAGARAJA (D K N AND ASSOCIATES)	
				In figures	In words
15	3.99	Providing and fixing Double shutter glass door of 12mm thick frosted toughened glass of approved make. The door is fixed by using any approved make hardware fitting like patch fitting pivot, floor machine, locking arrangements and suitable SS door rails with floral glass etching for 1/3 portion of door area etc complete. The rate includes cost of all materials labour, hire of tools & machineries, as per specifications etc complete The rate includes cost of all materials, labour, hire of tools & machineries as per specifications	Sqm	9740.00	Rupees Nine Thousand Seven Hundred Forty Only
16	6.39	Providing Sal wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM complete as per specifications	Cum	69315.00	Rupees Sixty Nine Thousand Three Hundred Fifteen Only
17	6.39	Providing and fixing factory made splendoor of solid core single leaf rigid composite polymer laminated sal wood, door shutter of required thickness, manufactured out of solid core door conforming to IS 2202 (Part-1) 1991, laminated with 0.8 mm thick polymer, termite, water resistant and fire retardant with superior gluing based on vacuum lamination technology and with various pre moulded design on both faces conforming to IS 6307-1985, using adhesive conforming to IS 4835-1979 and door shutters tested in conformation to IS 4020-1994. The finish of shutters will be TEAK/CEDAR/ROSE WOOD/WALNUT, plain colors WHITE/IVORY/BEIGE/LIGHT GREY. Excluding cost of fixtures and inclusive of supply of shutters to respective work spot. with door shutter 35mm thick	Sqm	4354.00	Rupees Four Thousand Three Hundred Fifty Four Only
18	12.65	Providing & fixing factory made SOLID PVC Door frame of size 50x47mm with a wall thickness of 5mm, made out of extruded 5mm rigid PVC foam sheet mitered cut at corners & jointed 2 Nos of 150mm long brackets of 15x15mm M.S Square tube, the entire door frame to be reinforced with 19x19mm M.S Square tube of 19 gauge. The door frame to be fixed to the wall using M.S. Screws of 65/50mm size complete as per manufacturers specification & direction of Engineer-in-charge	Sqm	540.00	Rupees Five Hundred Forty Only
19	12.65	SOLID PANEL PVC DOOR SHUTTER Providing & fixing 35mm thick factory made rigid foam Panelled Door Shutters made from M.S. tube of 19 gauge thickness, size 19x19mm for styles and 19x15mm for top & bottom rails, covered with heat moulded PVC channel of 5mm thick sheet & 90 x 50mm wide to form styles & 5mm thick & 75mm wide PVC Sheets for top rail, lock rail & bottom rail on either side & 5mm thick 25mm wide PVC sheet as gap insert for top rail & bottom rail, Panelling of 5mm thick PVC sheet fitted in the M.S. Frame, beaded to the styles & rails with 5x25mm PVC sheet beading on either side & joined together with solvent cement adhesive etc. Complete as per manufacturers specification & direction of Engineer in charge fixed to frames with 3 nos of 75 m m Aluminium hinges.	Sqm	3183.00	Rupees Three Thousand One Hundred Eighty Three Only

Scanned by TapScanner

	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. D K NAGARAJA (D K N AND ASSOCIATES)	
				In figures	In words
20	11.00	Fixing of frames in an existing opening including embeeding frame in floor and walls after cutting masonry for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and down size granite metal painting two coats of coal tar to sides of frame, making good the damages to walls and floor as required and disposal of the debriee with lead upto 50 m including cost of materials, labour charges, complete as per specifications	Nos	1568.00	Rupees One Thousand Five Hundred Sixty Eight Only
21	39.75	3 track x 2 Panel with mesh Specification for UPVC windows Providing & fixing of 3track x 2-panel sliding windows made out of multi chambered UPVC(Matching to RAL-9016) sections and with minimum TiO2(Titanium Dioxide) at 6PHR with TPV(Thermo Plastic Vulcanized) and lead free, gaskets -grey colour having isolated drainage and reinforced with Galvanized Iron profile through-out the window frame. The outer frame havings overall size of 108mm width x 45mmheight with reinforcement of 1mm thickness and Sash with overall size of 39mm x 75mm with GI reinforcement of 2mm and mesh sash of size 30mm x 48.5mm. Glazing bead for fixing of glass shall be of size 20mm x 24mm. Windows shall be provided with 5mm plain float glass, standard hardware& single point locking system with touch lock. Wall thickness of frame & sash shall be of 2mm-2.5mm. Maximum possible size – 2419mm x 2119mm.	Sqm	6496.00	Rupees Six Thousand Four Hundred Ninety Six Only
22	4.50	Specification for UPVC ventilator with fixed Louvers Providing & fixing of louvered ventilator made out of multi chambered UPVC(Matching to RAL-9016) sections and with minimum TiO2(Titanium Dioxide) at 6PHR with TPV(Thermo Plastic Vulcanized) and lead free with gaskets -grey colour having isolated drainage and reinforced with Galvanized Iron profile through-out the ventilator frame. The frame having overall size of 39mm x 39mm with GI reinforcement of 1mm thickness Louver clip in Aluminium (powder coated in white) will be used on the frame along with plastic parts for fixing the 4 mm pin head glass. Wall thickness of frame shall be 2mm Maximum possible size – 1000mm x1000mm	Sqm	4157.00	Rupees Four Thousand One Hundred Fifty Seven Only
23	929.25	Providing and fixing M.S.grill work for windows and ventilators using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM complete as per specifications.	Kgs	115.00	Rupees One Hundred Fifteen Only
24	306.78	Providing and fixing Vitrified glazed tiles of approved make, quality & colour of size 900 x 900 x 12mm thick fixed on bed of 12mm thick cement mortar for flooring, skirting and jointed with neat cement slurry mixed with pigment to mach shade of tiles, including providing spacers at required interval and removing stains, including cost of all mateirals, mortar, labour, etc. Complete as per specification	Sqm	1032.00	Rupees One Thousand Thirty Two Only
25	61.36	Providing and fixing skirting of 300mm height using prepolished water cut/gang saw of 18mm thick grey granite 0.5mm wide chamfered width and depth and fixing in CM 1:4 of 20mm thick after chipping the walls etc., including cost of all materials, mortar, labour, curing etc., complete as per specification	m	871.00	Rupees Eight Hundred Seventy One Only

Scanned by TapScanner

		Item Name	Unit	Rate quoted by the bidder in figures	Rate quoted by the bidder in words
28	49.04	Providing Cantonic tiles of approved make and hue for roofing, inserts of single pitch ventilator laid on a row of 12mm thick cement mortar 1:3 mix, hose pointing with white cement using colour pigment including cost of materials, labour charges, carriage complete as per specifications. For Cantonic tiles of size 420mm x 330mm thick	Sqm	1361.00	Rupees One Thousand Three Hundred Sixty Seven Only
29	185.01	Providing, carving, detailing, cove of steps with colour glazed tiles on 12mm thick cement plaster 1:3 and jointed with white cement slurry over existing rough plaster surface using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications (Glazed tiles should be 6mm thick with border of size 30 x 10 cms	Sqm	1870.00	Rupees One Thousand Eight Hundred Seventy Only
30	50356.00	Fabrication supplying and erecting M.S. tubular trusses of all sizes as per approved drawing & design with prefabricated steel applications using quality material and are durable reliable and corrosion and abrasion resistant. Welding shall confirm to latest structural welding code. Quality shall be on various parameters like shape, size, design gauge and polish. The white trusses is anchored in RCC column by using 4 nos of M.S. anchor bolts at each support with 16mm thick base plate and shoe plate. The work includes cutting, straightening, bending in position of M.S. pipes and welding wherever necessary and applying one coat of redoxide primer coat to all the members including cost of all materials, labour charges, and hire charges of machineries for cutting, welding, grinding and erection equipments, with all lead and lift, transportation etc., complete as per specification	Kgs	132.00	Rupees One Hundred Thirty Two And Paise Sixty Only
31	663.01	Providing and erecting of pre painted Galvolume (Al-Zn Composite) profiled sheet of approved make 1050 mm width (1000 mm cover width), 28-30 mm crest height with crest distance of 200 mm c/c with 2 ribs at the centre for stiffening. The total coated thickness (TCT) of the sheet will be 0.47 mm +/- 0.02 mm tolerance Zinc-Alu Alloy coating AZ150 gsm as per ASTM 1397/A755-550 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 20-22 microns using self drilling/self tapping screws of 25 mm length, to be fixed over the existing purlins, rafters, channels and trusses with all lead and lift and directions of the Engineer-In-charge of the work	Sqm	794.00	Rupees Seven Hundred Ninety Four Only
32	100.00	Providing, fabricating and fixing of stick type structural glazing using Aluminium Extrusions of 63.5 mm x 58.00 mmx 2.25 mm at 1.73 kg/mtr for vertical and Horizontal members and 63.5 mm x 38.1 x 1.35mm at 0.755 kg/Mtr, as outer frame with Electro Anodized Paint coated black finishing using 5mm thick imported glass reflective hard coated ocean blue raw glass with all necessary accessories like ultra glass Silicon sealant of Space tape, Masking tape, Galvanized Anchor bolt, machine screws, 6mm thick M.S. angle 50mm x 150mm x 6mm M.S. Galvanized L Brackets, structural sealant setting clocks Sealants, wall connection etc. complete.	Sqm	7623.00	Rupees Seven Thousand Six Hundred Twenty Three Only
33	11.00	Providing and fixing of Door locking arrangement(pair) (As per item no 39A)	Each	583.00	Rupees Five Hundred Eighty Three Only
34	83.00	Providing and fixing of Handles powder coated 150mm long (As per item No.39B)	Each	53.00	Rupees Fifty Three Only

Scanned by TapScanner

		Item Name	Unit	Negotiated Rates quoted by Sri. D K NAGARAJA (D K N AND ASSOCIATES)	
				In figures	In words
	13.00	Providing and fixing of Hinges 3" heavy duty(Page No XV item No 33)	Each	33.00	Rupees Thirty Three Only
	34.00	Providing and fixing of Hook bolts MS (Page No XV item No 34)	Each	34.00	Rupees Thirty Four Only
	107.00	Providing and fixing of Towel bolt 300mm long(page No XVI item No 60)	Each	107.00	Rupees One Hundred Seven Only
	167.00	Providing and fixing Chorinated Poly Vehyl Chloride (CPVC) pipes conforming to IS 15778 having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings, this includes jonning of pipes and fittings with lone step solvent cement, trenching, refilling & testing of joints complete. (external work) - 20mm nominal OD pipes	M	167.00	Rupees One Hundred Sixty Seven Only
	1087.00	Providing white vitreous china clay Indian pattern squatting urinals with white glazed foot rests of approved quality and make conforming to ISI specifications and fixing in Position with M-15 as directed of size 50.8 cms X 36 cms X 10.16 cms - A Grade (Rate includes cost of all materials and conveyance to work spot). (P.No. 59, I.No. 12.110 of PWD SR 2015-16)	Each	1087.00	Rupees One Thousand Eighty Seven Only
	326.00	Providing and fixing C.I. Nahani trap of approved make conforming to ISI specifications and construction of Cistern in M-15 as per directions. (Rate is inclusive of cost of materials and fixtures and conveyance of materials to work spot). - 12.5cms x 7.5cms	Each	326.00	Rupees Three Hundred Twenty Six Only
	326.00	Providing and fixing 7.5 cms to 15.00 cms dia NP grating 100 mm dia.	Each	326.00	Rupees Three Hundred Twenty Six Only
	270.00	KSRE13-6.1-2 Providing and fixing in position brass bib cock of approved quality 25mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No KBS 13.2.2 / 13.3	Each	270.00	Rupees Two Hundred Seventy Only
	3604.00	KSRE 11-11.1 Providing and fixing white vitreous china clay flat back wash down size 630x455mm with a pair of 15mm C.P brass pillar taps with C.I./ M.S brackets, 32 mm C.P brass waste of standard pattern, painting of fittings and brackets cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11	Each	3604.00	Rupees Three Thousand Six Hundred Four Only
	5673.00	KSRE 12.5 Providing and fixing white vitreous china clay water closet European type (Pedestal type P-trap) with solid plastic seat and lid CP brass hinges rubber buffers 110ltr low level P.V.C flushing cistern (all are approved make) with fittings (C./M.S bracket) 40mm diameter flush bend with fittings and clamps, overflac over flow arrangement with specialand 25mm mosquito proof coupling of approved design painting of fitting and brackets cutting and making good all the wall floor wherever required including cost of all materials labour complete as per specification	Each	5673.00	Rupees Five Thousand Six Hundred Seventy Three Only
	1433.00	Providing and fixing to wall, ceiling and floor any type of pipes P.V.C pipes (K 10 kg/sq.cm working pressure) chlorin plast / Maxim or equivalent make with pipe fittings, wall clips, making good the wall, ceiling and floor including cost of all materials with labour cutter etc	m	1433.00	Rupees One Thousand Four Hundred Thirty Three Only

Contractor

Scanned by TapScanner

		Item Name	Unit	Supplied Rates quoted by M/s [illegible]	
				in figures	in words
[illegible]	[illegible]	[illegible] Providing and fixing [illegible] for rectangular sheet valve mild steel plate moulded frame of approved make and shutter with 5mm thick hard board backing [illegible] duly clad in rexine as per specification complete as per specification	No	[illegible]	Rupees One Thousand Six Hundred Ninety Five Only
[illegible]	4.26	Supply and installation of Treadmills of Speed 0.5 - 25km/h (0.3 - 16mi/h), Acting (0.5hp max) Power of the motor source Rate: 0% - 18% Input power 120V or 220V (50Hz-60Hz) Features: self tracking tube, ambient glycerin USB socket, shock absorption system, convenience function, wireless mobile recharge, wireless heart measurement, pre-lubricated deck, Running area (W)30 x L(60)inch (31.49.5") maximum user weight 300kgs Display info: time, distance, calorie, speed, incline, heart rate, inclusive of All Taxes and Transportation Charges	Each	[illegible]	Rupees Seven Lakh(s) Nineteen Thousand Six Hundred Thirty Only
46	1.26	Supply and Installation of Bike of BH H775 of Technical specifications, resistance level: 8 levels, no-friction magnetic resistance, power: 1.5 volts x 2 aa size battery, fly wheel: 5 kgs precision balanced Drive system: center design drive, super silent poly-v belt driven, Pedals: self balanced with adjustable straps, Seat: ergonomically designed easy seat with, fan back cushion contoured for lumbar support with horizontal slide adjustment Hahdle bars: side handle bar with contact heart rate sensor and u bar style front Handle, display: dot display, single window computerized console, Display: multi read out instantly displays time, speed, distance, calories, pulse, odo and scan, user weight: 100 kgs, Frame structure: extra sturdy and stable steel frame construction, for maximum durability and stability, frame to be finished with proprietary two coat powder process, inclusive of All Taxes and Transportation Charges	Each	[illegible]	Rupees Two Lakh(s) Eighty Thousand Five Hundred Ten Only
47	1.26	Supply and Installation of Rowing of Inspire Fitness Cross Rower, Heavy-duty steel, COLOR-Matte black, chrome & red FINISH-Electrostatic powder coat, FLYWHEEL 30 lbs (14 kgs) with silent drive chain, RESISTANCE SYSTEM-Magnetic, Display: LED touch panel (9V, 4D size batteries), BLUETOOTH-Ready to connect to heart rate monitoring devices, SEAT-Ht Tablet, water & personal item storage, Tilt upright, on front and to store, MAX USER WEIGHT 300 lbs (136 kgs), WARRANTY: Residential: Limited 10y frame, 3y parts, 1y labor, Light Commercial: 10y frame, 2y parts, 1y labor, Full Commercial: 5y frame, 1y parts, 6m labor, SIZE/WEIGHT: 226 lbs (103 kgs), Inclusive of All Taxes and Transportation Charges	Each	[illegible]	Rupees Two Lakh(s) Ninety Three Thousand Seven Hundred Twenty Six Only
48	1.26	Supply and installation of Lever Seated Chest Press, Product size: 54" (137 cm) L x 31" (79 cm) W x 76" (193 cm) H, Weight: 280kg (618lb), Stack weight: 100kg (220lb), Material: Frame: 3mm x 100 x 50 mm steel tubing, Adds material double sided thick steel shell and foam, Ergonomic foam, Chest pad: Contoured, high-load moulds handle angle, Handles: Ergonomic handles with rubber grip, Footplate: High-load moulds handle angle, Footplate: Ergonomic high-load moulds handle angle, Footplate: Ergonomic high-load moulds handle angle, Footplate: Ergonomic high

		Item Name	Unit	Negotiated Rates quoted by Sri. D K NAGARAJA (D K N AND ASSOCIATES)	
				In figures	In words
		Supply and Installation of Lat Pull Specifications Dimensions W1 085 x L1 615 X H2 242 mm (43 1"x63 6"x88 3") Product Weight : 255Kg (562lb) Stack Weight 100kg (220lb) Features Weight adjustable thigh pads providing stability Greater feeling of thigh pad grips ABS material both-side stack cover Inclusive of All Taxes and Transportation Charges	Each	369317 00	Rupees Three Lakh(s) Sixty Nine Thousand Three Hundred Seventeen Only
50	1.00	Supply and Installation of Smith Machine of Specifications Dimensions W1 844 x L1 350 X H2 230 mm (72.6"x53.2"x87 8") Product Weight 188Kg (415lb) Features Rotating handle bar helping exercise start/stop 10kg of weight helping user's exercise 12 racking positions and 4 plate storage horns Improved feeling of 10kg dual weight clapper Inclusive of All Taxes and Transportation Charges	Each	397826 00	Rupees Three Lakh(s) Ninety Seven Thousand Eight Hundred Twenty Six Only
51	1.00	Supply and Installation of Assisted Chin/Dip of Specifications Dimensions : 1,137×L1,318×H2,273mm (44.7×51.8"×89.4"") Product Weight 256kg (564lb) Stack Weight 75kg (165lb) Features Rotating handles allow users of all the size Dual chinning handles providing variety of exercise Knee pads designed for easy start and finish of workout ABS material both-side stack cover Inclusive of All Taxes and Transportation Charges	Each	474281.00	Rupees Four Lakh(s) Seventy Four Thousand Two Hundred Eighty One Only
52	1.00	Supply and Installation of Arm Curl of Specifications Dimensions W1 410 x L1,080 X H1,506 mm (55.5"x42.5"x59.3") Product Weight 226Kg (498lb) Stack Weight 75kg (165lb) Features Much improved handle angle for muscle contraction Separately moving handles Comfortable start/stop handles ABS material both-side stack cover Elbow pads for stability 10-steps gas shock absorber type seat position adjustment Inclusive of All Taxes and Transportation Charges	Each	462313.00	Rupees Four Lakh(s) Sixty Two Thousand Three Hundred Thirteen Only
53	1.00	Supply and Installation of Abdominal of Specifications Dimensions : W1 284 x L1,246 X H1,506 mm (50.6"x49.1"x59.3") Product Weight 237Kg (523lb) Stack Weight : 100kg (220lb) Features Elbow pads and large handles providing stabilization 10-steps gas shock absorber type seat position adjustment ABS material both-side stack cover Inclusive of All Taxes and Transportation Charges	Each	413376.00	Rupees Four Lakh(s) Thirteen Thousand Three Hundred Seventy Six Only
54	1.00	Supply and Installation of Elliptical of Resistance Level. 20 Levels, Power Requirements 120 volts Set up height 4, 10 Workout Programs Manual, random, interval, custom interval, 10K Features Heart rate monitoring, space-efficient footprint, patented Multi Grip handlebars, water bottle holder, Workout boosters X-Mode, Arm Blaster, Glute Kicker, Dedicated logic programming, quick start, auto quick start, cool down, heart logic intelligence, wireless & Digital heart rate, Heart rate-controlled programs, maximum user weight 180kgs. Inclusive of All Taxes and Transportation Charges	Each	286384.00	Rupees Two Lakh(s) Eighty Six Thousand Three Hundred Eighty Four Only
55	300.00	Supplying and fixing of PVC casing and capping on the wall or ceiling using necessary materials like bends, screws at an interval of 300mm etc as required 25mm (P.NO 3.1 8.2)	Mtr	27.00	Rupees Twenty Seven Only

Contractor

Scanned by TapScanner

Sr. No.	Item No.	Item Name	Unit	Negotiation Rates quoted by SH. D K NAGARAJA (D K N AND ASSOCIATES)	
				In figures	In words
		Point wiring using Double core wire without switch. Supplying and wiring vitrified / PVC system in existing PVC Conduit / casing capping using 1.5 sq. mm. COPPER conductor flexible multistrand FR / PVC insulated 2X1 Sqmm Cable conforming to IS 694/1990 without switch (by other end of the wires shall be terminated with suitable size ferrule in a wood/PVC board block connection for each outlet. GROUP A Short point upto 3.5m from tapping point to out let via switch (P No 5, (No 2)	Each	152.00	Rupees One Hundred Fifty Two Only
58	22.20	Medium point above 3.5M upto 6M from tapping point to out let via switch (P No 5, (No 2.1))	Each	227.00	Rupees Two Hundred Twenty Seven Only
59	16.00	Long point above 6M upto 10M from tapping point to out let via switch (P No 5, (No 2.1))	Each	354.00	Rupees Three Hundred Fifty Four Only
60	120.00	Wiring for light / power circuit using one of FRLS PVC insulated 1100V grade multistrand Copper with low conductor resistance single core wire in open or concealed system of wiring with specified IS:694-1990 & conforming to GTP of GROUP -A 1.5 sqmm (P No. 5 (No 2.6.2))	Mtr	19.00	Rupees Nineteen Only
61	300.00	2.5 sqmm (P No. 5 (No 2.6.3))	Mtr	30.00	Rupees Thirty Only
62	1200.00	4 sqmm (P No. 5 (No 2.6.4))	Mtr	44.00	Rupees Forty Four Only
63	960.00	Supplying and fixing powder coated / galvanized metal pdx suitable for mounting modular switch plates. The box should be firmly held mounted after due groove cutting in Brick/Stone/C wall 1-3Way/P NO	No	96.00	Rupees Ninety Six Only
64	5.00	4-5Way/P NO (P No 5, (No 3.6.2))	No	103.00	Rupees One Hundred Three Only
65	4.00	6Way/P NO (P No 5, (No 3.6.3))	No	148.00	Rupees One Hundred Forty Eight Only
66	12.00	10-12Way/P NO (P No 5, (No 3.6.5))	No	168.00	Rupees One Hundred Sixty Eight Only
67	8.00	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting bach plate with required nos. of machine screws, bolts nuts etc. complete on the existing metal/PVC box 1 to 3 Module/P NO (P No 5, (No 3.6.1))	No	115.00	Rupees One Hundred Fifteen Only
68	8.00	4 Module/P NO (P No 5, (No 3.6.2))	No	129.00	Rupees One Hundred Twenty Nine Only
69	12.00	6 Module/P NO (P No 5, (No 3.6.4))	No	212.00	Rupees Two Hundred Twelve Only
70	20.00	12 Module/P NO (P No 5, (No 3.6.5))	No	283.00	Rupees Two Hundred Eighty Three Only
71	15.00	Supplying and fixing 6 modular switch 5 pole/stepped electronic fan regulator/dimmer/step/pole socket etc on existing module switch plate as per IS 2032 and IS 1293 GROUP A 6Amps one way (P NO. 5 (No 3.7.1))	No	86.00	Rupees Sixty Six Only
72	15.00	6Amps two way (P NO. 5 (No 3.7.2))	No	92.00	Rupees Ninety Two Only
73	25.00	6Amps 3way one line (P NO. 5 (No 3.7.3))	No	100.00	Rupees One Hundred Only
74	4.00	Decoded Fan Regulator (P NO. 5 (No 3.7.4))	No	303.00	Rupees Three Hundred Three Only
75	1.00	15Amps one way socket (P NO. 5 (No 3.7.7))	No	120.00	Rupees One Hundred Twenty Only

Contractor

Scanned by TapScanner

	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. D K NAGARAJA (D K N AND ASSOCIATES)	
				In figures	In words
	12.00	6/16Amps universal socket (P.NO 16.3 7.10)	No	155.00	Rupees One Hundred Fifty Five Only
79	6.00	2' -14 watts (P No 25 , (No 4 29 1)	No	636.00	Rupees Six Hundred Thirty Six Only

Scanned by TapScanner